

MOLOKAI (MKK)(PHMK) 6 NW UTC-10 N21°09.17' W157°05.78'
454 B TPA—See Remarks Class I, ARFF Index A NOTAM FILE MKK
RWY 05-23: H4494X100 (ASPH-GRVD) S-30, D-48 PCN 12 F/B/Y/T MIRL

HAWAIIAN ISLANDS

P-2G

IAP, AD

0.4% up NE

RWY 05: REIL. PAPI(P4L)—GA 4.0° TCH 49'**RWY 23:** Thld dsplcd 593'. Brush.**RWY 17-35:** H3118X100 (ASPH) S-13 PCN 11 F/B/Y/T MIRL
0.6% up N**RWY 17:** Thld dsplcd 426'. Fence.**RWY 35:** Fence.**RUNWAY DECLARED DISTANCE INFORMATION****RWY 05:** TORA-4494 TODA-4494 ASDA-4494 LDA-4494**RWY 17:** TORA-3118 TODA-3118 ASDA-3118 LDA-2692**RWY 23:** TORA-4494 TODA-4494 ASDA-4494 LDA-3901**RWY 35:** TORA-3118 TODA-3118 ASDA-3118 LDA-3118**SERVICE: LGT** When twr closed ACTIVATE MIRL Rwy 05-23 and Rwy 17-35, REIL Rwy 05—CTAF. Rwy 05 PAPI not authorized 1.8 NM by landing thld due to rapidly rising terrain.

AIRPORT REMARKS: Attended 1500-0615Z. Be alert to egrets and pigeons on and in vicinity of arpt. TPA—small acft 1250(796) large acft 1950(1496). Arpt CLOSED to air carrier operations with more than 10 passenger seats 0530-1600Z except PPR call (808) 567-9660/9663. 24 hrs PPR for Division 1.1, 1.2, 1.3 explosives and 4 hrs PPR for other hazardous material in/out of arpt ctc (808) 567-6140/6008. Large acft with wingspan greater than 78' may not use Twy A or Rwy 05-23 for simultaneous ops. Mountain approximately 1280' MSL located 2.8 NM from threshold Rwy 05 on extended centerline. Standing water/ponding on Rwy 17-35 near Twy Echo during inclement weather.

AIRPORT MANAGER: (808) 872-3808**WEATHER DATA SOURCES:** ASOS (808) 567-6106**COMMUNICATIONS:** CTAF 125.7 ATIS 128.2**MOLOKAI RCO** 122.1R 116.1T (HONOLULU RADIO)® **HCF CENTER APP/DEP CON** 124.1**TOWER** 125.7 (1600-0430Z) **GND CON** 121.9**AIRSPACE:** CLASS D svc 1600-0430Z other times CLASS E.**RADIO AIDS TO NAVIGATION:** NOTAM FILE MKK.**(H) VORTAC** 116.1 MKK Chan 108 N21°08.29' W157°10.05' 067° 4.1 NM to fld. 1421/11E.

VORTAC unusable:

275°-285° byd 25 NM blo 3,500'

