

CRAIG—MOFFAT (CAG)(KCAG) 2 SE UTC-7(-6DT) N40°29.71' W107°31.30'

6198 B NOTAM FILE CAG MON Airport

CHEYENNE

H-3E, L-9E, 11E


IAP

RWY 07-25: H5606X100 (ASPH) S-35, D-40 PCN 12 F/D/X/T MRL**RWY 07:** REIL. P-line.**RWY 25:** REIL. PAPI(P4L)—GA 3.0° TCH 32'. Tree.**SERVICE:** FUEL 100LL, JET A LGT MRL Rwy 07-25 preset low ints, to increase ints and ACTIVATE MRL Rwy 07-25, REIL Rwy 07 and Rwy 25, and PAPI Rwy 25—CTAF.**AIRPORT REMARKS:** Attended Mon-Fri 1500-0000Z Sat-Sun irregularly. Wildlife on and invof arpt. Rwy 25 has +10' road 340' from thld obstruction, +41' trees 1185' from thld 50' left of centerline, +75' trees 4000' from thld. Cold temperature airport. Altitude correction required at or below -31C.**AIRPORT MANAGER:** 970-824-9148**WEATHER DATA SOURCES:** ASOS 135.425 (970) 824-2373.**COMMUNICATIONS:** CTAF/UNICOM 122.8

DENVER CENTER APP/DEP CON 120.475

CLEARANCE DELIVERY PHONE: For CD ctc Denver ARTCC at 303-651-4257.**RADIO AIDS TO NAVIGATION:** NOTAM FILE DEN.**HAYDEN (H) VORW/DME** 115.6 CHE Chan 103 N40°31.20'

W107°18.29' 248° 10.0 NM to fld. 7271/14E.

**CRAWFORD** (99V) 2 W UTC-7(-6DT) N38°42.25' W107°38.62'

6470 TPA—7270(800) NOTAM FILE DEN

DENVER

L-9E

RWY 07-25: H4900X20 (ASPH) LIRL(NSTD)**RWY 07:** VASI(NSTD). Trees.**RWY 25:** Hangar. Rgt tfc.**RWY E-W:** 2500X125 (TURF)**RWY E:** Rgt tfc.**RWY W:** Trees.**SERVICE:** S2 LGT Arpt lgts opr dusk 0800Z. Rwy 07 1 VASI box on left and right side of rwy. For local operators only or PPR call 970-921-7700. Rwy 07-25 has LIRL on N side on rwy for center 1600' beginning 1200' east of Rwy 07. No thld lgts. Rwy 07-25 3800' usable for ngt ops. Rwy 07-25 NSTD LIRL, Rwy 07-25 has LIRL only on north side on rwy for center 1600' beginning 1200 east of Rwy 07 thld. No thld lgts. Rwy 07-25 3800' usable for night opr. Rwy 07 NSTD VASI, has 1 VASI box on left and right side of rwy. For local opr only or PPR call 970-921-7700.**AIRPORT REMARKS:** Attended continuously. Rwy 07-25 west 1300' only 25' wide. Glider ops invof arpt. Land to the east tkf to the west winds permitting. 100LL fuel avbl for emerg use only. Pedestrians, motor vehicles, deer and wildlife on and invof arpt. Unlimited vehicle use on arpt. Rwy West has +35' building 170' west of thld 30' left, +10' road 100' from thld centerline. +15' tree 150' from thld OB. -8' to -20' terrain off both sides of first 674' of Rwy 25 end. E-W rwy consists of +12 inch alfalfa vegetation during various times of the year. Rwy 07 has 40' trees and -10' to -20' terrain 20' right of rwy first 150'. Rwy 25 has +20' trees 300' from thld OB. Rwy 25 has 50' water tanks 900' from thld on extended centerline. +2' electric box 150' from thld 30' right. +10' road 100' from thld OB. Rwy E has +20' trees at thld 150' right of centerline, +10' trees 150' from thld OB.**AIRPORT MANAGER:** 970-921-7700**COMMUNICATIONS:** CTAF/UNICOM 122.8**CLEARANCE DELIVERY PHONE:** For CD ctc Denver ARTCC at 303-651-4257.**RADIO AIDS TO NAVIGATION:** NOTAM FILE MTJ.**MONTROSE (H) VORW/DME** 117.1 MTJ Chan 118 N38°30.39' W107°53.96' 033° 16.9 NM to fld. 5713/12E.
vDME unmonitored.

DME unusable:

011°-090° byd 26NM blo 15,000'

190°-250° byd 25 NM blo 15,000'

VOR unusable:

060°-090° byd 26NM blo 16,000'

190°-250° byd 25 NM blo 15,000'