

**DOUGLAS MUNI** (DGL)(KDGL) 2 E UTC-7 N31°20.56' W109°30.39'

**PHOENIX**  
H-4X, L-5D

4173 B AOE NOTAM FILE PRC

**RWY 03-21:** H5760X75 (ASPH) MIRL

**RWY 03:** PAPI(P4L)—GA 4.0° TCH 40'. Brush. Rgt tfc.

**RWY 21:** PAPI(P4L)—GA 4.0° TCH 50'. Brush.

**RWY 18-36:** 4095X100 (DIRT)

**RWY 18:** Brush.

**RWY 36:** Brush. Rgt tfc.

**SERVICE:** FUEL 100LL, JET A LGT Dusk-dawn. PAPI Rwys 03 and 21  
OTS indfy.

**AIRPORT REMARKS:** Attended Mon-Fri 1300-2200Z, For svc after hours call 520-368-6015. Personnel on ATVs near acft opr areas-unrestricted. Mountains 1 1/2 miles east. 24 hr 100LL avbl with major credit card. Rwy 03-21 has 1"- 6" cracks across rwy. Rwy 18-36 has +4' brush, rocks and uneven surface for 3/4 of rwy length. Rwy 21 50' twr 1350' from thld 550' left lgtd. Rwy 18-36 brush on both sides 70 ft from centerline full length of rwy. Rwy 18-36 surface rough and rutted. Rwy 18-36 +3 ft bump 300 ft from Rwy 18 thld. Rwy 18-36, 2 ft bump crossing twy to Rwy 03-21. Flight notification svc avbl.

**AIRPORT MANAGER:** (520) 368-6015

**COMMUNICATIONS:** CTAF/UNICOM 122.8

**RCO** 122.6 (PRESCOTT RADIO)

**RADIO AIDS TO NAVIGATION:** NOTAM FILE DUG.

**(VL) (H) VORTACW** 108.8 DUG Chan 25 N31°28.36' W109°36.12' 135° 9.2 NM to fld. 4131/13E.

TACAN AZIMUTH unusable:

045°-065° byd 26 NM blo 10,000'

065°-095° byd 28 NM blo 9,500'

355°-010° byd 35 NM blo 11,300'

DME unusable:

045°-065° byd 26 NM blo 10,000'

065°-095° byd 28 NM blo 9,500'

355°-010° byd 35 NM blo 11,300'

VOR unusable:

046°-063° byd 40 NM blo 11,000'

046°-063° byd 49 NM blo 16,000'

046°-063° byd 63 NM

253°-263° byd 40 NM blo 16,000'

253°-263° byd 66 NM

264°-277° byd 40 NM

278°-288° byd 40 NM blo 16,000'

278°-288° byd 52 NM

305°-316° byd 40 NM

345°-045° byd 40 NM

